G. R. S. 59]

GPB—15,000—20 12 13

GENERAL AND REVENUE SECRETARIAT.

19D/-02
(Muzrai)

File No. 74

Serial Nos. 1—6

Papers Filed.

*Month*_____

SUBJECT.

Sanctions are solicited for Rs 300/- for the repairs of the Compound wall and other petty repairs of the Sri Ranjindeswara Swamy Temple at Devanahalli Town

PREVIOUS REFERENCES

LATER REFERENCES

S.R.I

In obedience to your orders I proceeded to Devanhalli and inspected the Sree Nanjundeswara Swami temple at Devanahalli and beg to submit the following report:—

This temple — a muzrai institution — is an important one and it is in a very dilapidated condition. The whole roof is leaky and the images are drenched with rain water. A side wall constructed of mud has cracked in 2 or 3 places and the compound is overgrown with wild plants. I have accordingly prepared an Estimate for Rs 300 to carry out the following urgent repairs:—

(1) Roofing the temple with chunam concrete with an ordinary parapet allround

(2) Constructing the side wall with stone in mud.

(3) Constructing a small compound wall only in the front along with some petty repairs

Bangalore
13th Septr 1898

Balakrishna Rao
Muzrai overseer

Order SK 2

No 383
dt 19. 9. 98
Ee.

The accompanying Estimate amounting to Rs 300 prepared under the personal instructions of the Murrai Superintendent for repairing the Sree Nanjundeswara swami temple at Devanhalli is sanctioned, the charge being met from the State-Grant of ~~Rs~~ 15000 sanctioned in Govt Pro no: 1087 Murr 105-92 dt 18th February 1898 for the repairs of Murrai Buildings in the Province during the year 1895-99.

2 The amount sanctioned above will be paid on presentation of a bill duly signed by the Murrai Superintendent

The Comptroller Mysore Govt with a of abstract Estimate.

Murrai Secy.

Measurement of work done for repairing the Sri Nanjundeswara Swamy temple at Devanhalli.

Details	No.	Dimension			contents	Total
Constructing with stone in mud. one side wall of the Navarangam-	1	34.	1½	8.	408	
Total						408
Roofing with concrete	1	50	30	(½)	1500	
Total sqrs						15·00
Constructing ordinary parapet. Total R/ft.						160
Putting new punjewood doors.	4	6¼	3½	-	81	
Total S/ft.						81
Pointing L.S. Sqrs						10·00
Constructing compound wall- Total R/ft.						60

Abstract.

Items	Per	Rate	@	cost.
Constructing the side wall of the navara fogam with stone in mud.	CH:	- 14	408	45
Roofing with concrete and flat tiles including plastering.	Sqr.	8 - -	15.00	120
Constructing ordinary parapet	RH:	- 2 -	160	20
Putting new doors of jungle wood with hinges bolts &c complete.	SH:	- 6 -	81	30
Pointing with chunam.	Sqr	- 12 -	10.00	8
Constructing the compound wall	R.H:	- 14 -	60	53
Putting a new gate.	1			10
Total				286
Contingencies at 5%				14
Grand total Rupees				300

Bangalore
10th Septr 98

Balakrishna Rao
Murrai overseer

Estimate of the probable cost of repairing the Sree Nanjundeswara Swami Temple at Devanhalli.

Details	No.	Dimension			Contents	Total.
Constructing with stone in mud one side wall of the navarangam.	1	34	1½	8	408	
Total						408
Roofing with concrete	1	50	30	(½")	1500	
Total Sqrs						15-00
Constructing ordinary parapet Total Rft						160
Putting new junglewood doors.	4	6¼	3½		81	
Total Sft						81
Pointing L.S. Sqrs						10.00
Constructing compound wall Total Rft						60
Foundation for do	1	1	1½	2	3 at	
					0-1-6	0-4-6
Superstructure	1	1	¾	4	3 at	
					0-1-9	0-5-3
Plastering	1	2	4	-	8 at	
					2-4-0	0-3-0
Coping ordinary —						0-1-3
Total cost of each Rft of compound wall						0-14-0

విజ్ఞాపనచేసుకొనుచున్నది ఏమనగా—
తా 15-12-98 ఆదివారం నాడు జరుగు తిరుపతి—

Measurement.

Abstract of ~~Estimate~~ for the repairs to the Sri Narayanaswamy Swami temple at Devanhalli

in Devanhalli Taluk Bangalore District

Particulars	Per	Rate Rs.	a.	p	Quantity	Cost Rs	a.	p.
Constructing with Stone in mud. the side wall of the navarangam	Cft:		1	9	408	44	10	0
Roofing with concrete and flat tiles including plastering	Sqr	8	.	.	15.00	120	.	.
Constructing ordinary parapet:	Rft	-	2	.	160	20	-	.
Putting new doors of jungle wood with hinges bolts &c. Complete.	Sft:	-	6	-	81	30	6	0
Chunam pointing.	Sqr	-	12	.	10.00	7	8	.
Constructing compound wall with plastering &c Complete	Rft:	-	14	-	60	52	8	0
~~Putting a new gate.~~	~~Ls.~~					~~10~~		
Total								275 ~~295-0~~

Rupees Two hundred and ~~eighty~~ seventy five only

Balakrishna Rao

Sanctioned in Govt. Proceedings No. ——— ~~dated~~

Murray overseer

measurement

Abstract of ~~Estimate~~ for the repairs to the Sri Narayanaswami Swami temple at Devanhalli

in Devanhalli Taluk Bangalore District

Particulars	Per	Rate			Quantity	Cost		
		Rs.	a.	p		Rs	a.	p.
Constructing with stone in mud the side wall of the Navaranga	Cft.		1	9	408	44	10	.
Roofing with Concrete and flat tiles including plastering.	Sqr	8	.	.	15.00	120	.	.
Constructing Ordinary parapet.	Rft.	-	2	-	160	20	.	.
Putting new doors of jungle-wood with hinges, bolts &c Complete	Sft.	-	6	-	81	30	6	0
Chunam pointing.	Sqr	-	12	.	1000	7	8	-
Constructing compound wall with plastering &c complete.	Rft.	-	14	.	60	52	8	-
		Total Rupees —				275	0	0

Rupees two hundred and seventy five only —

(Sd) Balakrishna Rao

Murrai overseer

copy

Attested

sd Murrai Secretary —

~~Sanctioned in Govt. Proceedings No.~~

Maz A.]

The ..... Government ..... of ..... Mysore ..... Dr.

Particulars.	Amount.	Remarks.
To.		
On account of the repairs executed to the Sri Nanjundeswara Swami Temple at Devanhalli as per abstract measurement list, copy of which is appended.	275 - -	Work sanctioned in Govt Pro no 383 dated 19th Septr 98
To be made payable at the State Huzur Treasury		As
Bangalore 2 Dec 993		Maraai Superintendent

MUZRAI

189

SL 5

From

The Secy to the Govt of Mysore

To

The Comptroller

Dated 10

Despatched 10 Feby

Received

General No. 946

Muzrai F. No.

Enclosure No. 2

Govt Pro: no: 383
dated 19th Septr 1898
sanctioning an Estimate
for Rs 300 for repairing
the Sri Nanjundeswara
Swami temple at
Devanhalli

Has the honor to
forward herewith a
bill duly countersigned
for Rs 275 on account

of the works executed
towards the repairs
of the temple sanctioned
in the above and to
request that the bill
may be audited and
returned to this office
for payment.

By order

Mofrai Secretary

ను బుద్ధిగికోగదుఁజేర్చుంటిరేనే
దిదుగని క్షేమముగొంటి మంత్రినిదుభాం
దేమోంవలను లంటాంన్నేనునీర్ణ
రదిందనగనిగోవరతక్కిద్దుటయి
లమేందుమవ్విగారనిక్షేంభ్వర
నిలతి.

13 నవంబరు 1897.

[illegible]

[illegible]

S. Varadachar

S Vulakanta Rai